
Redbud Trail/River Street/Fourth Street Intersection Improvements: Installation of a New Traffic Signal and Realignment of Fourth Street

The City of Buchanan will begin the realignment of Fourth St. and the installation of a new traffic signal at the Redbud, River and Fourth St. intersection. The project start date is Monday, March 11th, and estimated completion is June 29th. Redbud and River Sts. will remain open during the project and traffic control personnel will be on site during significant construction operations. Fourth Street will be closed to thru traffic between Short St. and Redbud Tr. from April 18th to about May 18th. The dates for road closure are based on the contractor's progress schedule and allow for weather delays. The contractor will put a high priority on completing eliminate Fourth Street as quickly as possible to issues homeowners/residents impacted by the project. The on site inspector and the contractor will coordinate with homeowners and/or occupants to ensure access to each household is provided during the road closure.

The project Progress Schedule shows the work items in the order that they will take place, as well as the start and completion dates for each item. The project includes many components beginning with tree removal tagging and traffic signal staking. Installation of the traffic signal requires coordinated above ground and underground work by the project contractor as well as the various subcontractors, utilities with facilities in the project area, and municipal employees. Both Redbud and River Streets will remain open while the project is under construction, and motorists and pedestrians travelling through the site are advised to slow down and proceed with caution. As stated earlier, traffic control personnel will be on site as needed during the project work items taking place in the street(s) traffic lanes, but the success of the safety precautions taken depends on cooperation from everyone.

If you have any questions, please contact Debra Patzer at City Hall M-F at 269 695 3844 x 19 or dpatzer@cityofbuchanan.com. She will be in contact with the project engineer for the duration of the project and will see to it that your questions are answered.



Michigan Department of Transportation 1130 (01/18)

PROGRESS SCHEDULE information required by MDOT in order to establish a construction schedule.

Distribution: Original - Project Files

EILE 101

			FILE IOI	
CONTROL SECTION STU 11000	JOB NUMBER 130766	X INITIAL	UPDATE	
PROPOSAL ITEM NUMBER 1812 014	LETTING DATE 12/07/2018	5 - 1 - 1 - 1 - 1 - 1 - 1 - 1 - 1 - 1 -	***************************************	
OUTLINE OF PROPOSED ORDER OF WORK FOR CONTROLL	NG WORK ITEMS.			
CONTROLLING WORK ITEM ATTACHMENT		1	DURATION OF CONTROLLING OPERATION	
GALENDAR DAY WORK DAY CALENDAR DA		PATH START (Date/Work Day)	COMPLETE (Date/Work Day)	
Requests for Tree Removal Tagging and Traffic Signal Staking	3/11/19	3/21/19		
Traffic Control Devices and Setup.		3/22/19	3/24/19	
Tree Removals	3/25/19	3/27/19		
Traffic Signal Underground Mobilization	3/28/19	3/31/19		
Strain Pole Foundations and Underground Structures-*Hh, Pe	4/01/19	4/14/19		
Directional Bore Conduits	4/15/19	- 4/17/19		
Excavation Removals and Installs-*Ero Control, Removals, Underdrain, Structure Installs/Lowering & Milling		Milling 4/18/19	5/9/19	
Concrete- Curb, Gutter, Sidewalk, Ramp work		5/10/19	5/14/19	
HMA Installs, Hand Patching & Structure Adj.	5/15/19	5/18/19		
Pavement Markings, Signage Installs, Slope Restoration	5/19/19	5/22/19		
Traffic Signal- Strain Pole installation and Signal Installs/Removals		5/22/19	6/16/19	
Open to Traffic & Cleanup		6/17/19	6/28/19	
Final Completion		06/29/19	7/19/19	
REMARKS Open to traffic - HMA and Signals Complete: 6/28/19	the state of the s		· · · · · · · · · · · · · · · · · · ·	
Final Completion: 7/19/19				
• •				
	•			
CONTRACT COMPLETION 07/19/19	Conformance with pro-	gress clause and proposal (Maintain traffic	
WORKDAYS requirements) ☑ Yes PEN TO TRAFFIC DATE(S) 06/28/19 Overlapping dates? ☑ No ☐		No Ver If was attach le	retification	
WORKDAYS If A + B bid or rental (lane/bridge				
. + B bid? ⊠ No ☐ Yes, If yes, enter date(s):	with contract? Yes Incentive/ Disincentive?	No No		
.ane/Bridge/Ramp rental 🔲 No 🔲 Yes	If yes, enter maximum to		4	
CONTRACTOR NAME (PRINT) Scott Severance	LOCAL AGENCY		DATE	
SCOTT SEVERAL Emphaly signed by Smith, Sandaphee SCOTT SEVERAL Emphaly signed by Smith, Sandaphee SCOTT SEVERAL Emphasion Several Electrica des Several Elec	MDOT APPROVAL - CO	NSTRUCTION/PROJECT	DATE	